

Hydrodynamic and Water Quality Monitoring of the Lower Savannah River Estuary, August 2 through October 9, 1999

Prepared by:



Applied Technology & Management, Inc.
260 West Coleman Boulevard, Suite A
Charleston, South Carolina



Prepared for:



*Georgia Ports
Authority*

October 5, 2000

Hydrodynamic and Water Quality Monitoring
of the Lower Savannah Harbor Estuary,
August 2 through October 9, 1999

TABLE OF CONTENTS

Section	Page
1.0 Introduction	
1.1. Background and Site Description	1-1
1.2. Need for Data Collection	1-2
1.3. Authorization and Scope	1-2
1.4. Study Goals and Objectives	1-4
1.5. Results of the 1999 Data Collection	1-4
1.5.1 Preparation for the 1999 Data Collection Effort	1-5
1.5.2 Performing Data Collection Tasks	1-5
1.5.3 Hurricane Floyd	1-6
1.5.4 Water Chemistry Data Invalidated by Laboratory Error	1-8
1.5.5 QA/QC of the Data Presented in the Data Report	1-8
1.5.6 MTRG Conclusions	1-8
2.0 Field Procedures and Protocols	
2.1. Instrument Deployment and Siting Rationale	2-1
2.1.1. Continuous Water Quality and Hydrodynamic Stations	2-1
2.1.2. Water Chemistry Sampling Stations	2-3
2.1.3. ADCP Profiling	2-3
2.1.4. Special Events.....	2-4
2.2. Parameters Evaluated	2-5
2.3. Description of Instrumentation Used in Study	2-6
2.4. Regulatory and Agency Interaction and Approvals.....	2-7
2.4.1. Description of Permission Requested.....	2-8
2.4.2. Description and Conditions of Authorization	2-9
2.5. Dive and Field Crew Descriptions	2-11
2.5.1. Dive Crew Description	2-11
2.5.2. Field Crew Description	2-12
2.6. Instrument Mount Specifications	2-13
2.7. Instrument Servicing Protocols	2-15
3.0 Continuous In-Stream Hydrodynamic Data	
3.1. Location of Instruments.....	3-1
3.2. Deployment Dates	3-1
3.3. Mounting Methods	3-2
3.4. QA/QC Protocols	3-2
3.5. Water Surface Elevation	3-3
3.6. Continuous Currents	3-4
3.6.1. ADCPs in Lower Harbor	3-4
3.6.2. Nortek Current Meters upstream of I95 Bridge	3-5

4.0	ADCP Flow Monitoring	
4.1.	Location of Transects.....	4-1
4.2.	Profiling Dates	4-1
4.3.	Profiling Methodology	4-1
4.4.	ADCP Transect Data	4-3
5.0	Continuous In-Stream Water Quality Data	
5.1.	Location of Instruments.....	5-1
5.2.	Deployment Dates	5-1
5.3.	Mounting Methods	5-3
5.4.	QA/QC Protocols	5-4
5.5.	Temperature	5-7
5.6.	Salinity	5-7
5.7.	Dissolved Oxygen.....	5-8
5.7.1	Dissolved oxygen QA/QC	5-8
6.0	Hydrological and Meteorological Data	
6.1.	Location of Instruments.....	6-1
6.2.	Deployment Dates	6-1
6.3.	Mounting Methods	6-1
6.4.	QA/QC Protocols	6-3
6.5.	Freshwater Flows.....	6-3
6.6.	Rainfall	6-4
6.7.	Air Temperature.....	6-4
6.8.	Barometric Pressure	6-4
6.9.	Wind Speed and Direction	6-5
6.10.	Solar Radiation	6-5
6.11.	Relative Humidity	6-5
7.0	Continuous In-Stream Chloride and Bromide Data	
7.1.	Location of Instruments.....	7-1
7.2.	Deployment Dates	7-1
7.3.	Mounting Methods	7-2
7.4.	QA/QC Protocols	7-2
7.5.	Chloride	7-3
7.6.	Bromide	7-3
8.0	Water Chemistry Data	
8.1.	Sampling Locations and Background.....	8-1
8.1.1.	Location of Stations.....	8-1
8.1.2.	Sampling Period and Parameters.....	8-2
8.1.3.	Hurricane Floyd.....	8-2
8.2.	Sampling Protocol.....	8-3
8.3.	Water Chemistry Data	8-3
8.3.1	BOD5	8-4
8.3.2	CBOD5 8-5	8-5
8.3.3	Ammonia.....	8-5
8.3.4	Nitrate-Nitrite.....	8-5
8.3.5	TKN	8-6
8.3.6	Total Phosphorus.....	8-6

8.3.7	Orthophosphate	8-7
9.0	Special Events	
9.1.	Longitudinal Profiles At Pre-Established EPD Stations	9-1
9.1.1	Station Locations, Dates, and Protocols.....	9-1
9.1.2	Longitudinal Profiling Data.....	9-2
9.2	24-Hour Dynamic Sampling	9-3
9.2.1	24-Hour Station Locations	9-3
9.2.2	Parameters Sampled and Sampling Protocols	9-3
9.2.3	24-Hour Data.....	9-5
9.3	Marsh Exchange Event	9-5
9.3.1	Marsh Exchange Station Locations	9-5
9.3.2	Parameters Sampled and Sampling Protocols	9-6
9.3.3	Marsh Exchange Data	9-6
9.4	Primary Productivity Sampling.....	9-7
9.4.1	Station Locations and Sampling Period.....	9-7
9.4.2	Sampling Protocol	9-7
9.4.3	Chlorophyll-a Data.....	9-7
9.5	Cross-Sectional Distribution of DO and Salinity.....	9-8
10	LTBOD Data	
10.1	Location of Samples.....	10-1
10.2	Sample Dates	10-1
10.3	Sample Collection Protocol	10-1
10.4	LTBOD Data	10-3
11	USGS Monitoring Data	
11.1	Location of USGS Continuous Monitoring Stations	11-1
11.2	USGS Water Surface Elevation	11-1
11.3	USGS Salinity	11-2

APPENDICES

- Appendix A—Task Statements SEGP311, SEGP312, and SEGP313
- Appendix B—Specifications of Continuous Monitoring Stations
- Appendix C—Instrument Specifications
- Appendix D—Installation and Mounting Permits
- Appendix E—ATM Float Plan, Boating Procedures, and Safety Policy
- Appendix F— ADCP Protocol and QA/QC
- Appendix G— ADCP Measured Flows and Cross-Sectional Velocity Profiles
- Appendix H— ATM Calibration and Data Logging Sheets
- Appendix I—pH data for In-Stream Water Quality Stations
- Appendix J—Weeks 1 – 7 Water Chemistry Data
- Appendix K—Longitudinal Profiling Data at EPD Stations
- Appendix L—24-hour Sampling and Profiling Data
- Appendix M—Marsh Exchange Sampling and Profiling Data
- Appendix N—Primary Productivity Sampling and Profiling Data
- Appendix O—Cross-Sectional Profiling Data
- Appendix P—Turbidity data for In-Stream Water Quality Stations
- Appendix Q—Winkler Titration Data for Calibration of Dissolved Oxygen Sensors
- Appendix R—January 17, 2000 Report: Findings of In-Stream Water Chemistry Data – Field Collection August 2 through October 9, 1999
- Appendix S—September 29, 2000 Report: Final MTRG Recommendations for Responses to MTRG Comments on the 1999 Savannah Harbor Draft Data Report Received as of September 12, 2000.

LIST OF TABLES

Table Number	Title
1-1	Summary of the Data Collection Interruption Due to Hurricane Floyd (September 15 to 17, 1999)
1-2	Summary of Week 7 (October 5 to 9, 1999) Sample Results Invalidated by Laboratory Error
1-3.....	Continuous In-Stream Water Quality Stations Where Week 7 (September 13 to 17, 1999) Water Chemistry Samples Were Not Collected Due to Hurricane Floyd Evacuation (September 14 to 17, 1999)
2-1	Instrument Locations and Mounting Structures
2-2	Types of Instruments
2-3	Regulatory and Enforcement Agency Authorization
3-1	USGS Continuous Monitoring Stations Utilized in Adjustment of ATM Continuous Monitoring Stations for Water Surface Elevation, NGVD
4-1	Transect Dates, Tide Conditions and Locations
5-1	Servicing/Deployment Schedule for YSI Water Quality Instruments
6-1	Meteorological Station Deployment Locations and Dates
8-1	Dates of Sampling Events and Parameters Evaluated
8-2	Weeks 1-6 Conventional Parameters by Savannah Labs
8-3	Week 7 Parameters By AES
8-4	BOD5 Historical Comparison to 1999 In-Stream Data
8-5	NH3 Historical Comparison to 1999 In-Stream Data
8-6	NO3-NO2 Historical Comparison to 1999 In-Stream Data
8-7	TKN Historical Comparison to 1999 In-Stream Data
8-8	Total Phosphorus Historical Comparison to 1999 In-Stream Data
8-9	Orthophosphate Historical Comparison to 1999 In-Stream Data
9-1	Schedule of Profiling and Sampling at 24-Hour Sampling Stations

10-1LTBOD Sample Dates
10-2Total Number of LTBOD Samples
10-3LTBOD Stations and Marsh Exchange Transects
 River Miles

11-1USGS Station Locations and Parameters
 Measured
11-2Tidal Adjustment Between Mean Low Water and
 NGVD

LIST OF FIGURES

Figure Number	Title
1-1	Location Map of the Study Area
2-1a	GPA Station Locations (downstream of I-95 Bridge)
2-1b	GPA Station Locations (upstream of I-95 Bridge)
2-2.....	Dive Crew Servicing Photos
2-3	Spar Buoy Mount
2-4.....	Spar Buoy Installation
2-5.....	ADCP Bottom Mount
2-6.....	Basic Bottom Mount
2-7.....	Bridge / Pile Mount
2-8.....	4" PVC Instrument Mount
3-1a	Location of Hydrodynamic Instruments (downstream of I-95 Bridge)
3-1b.....	Location of Hydrodynamic Instruments (upstream of I-95 Bridge)
3-2	Photos of Hydrodynamic Mounts
3-3.....	Water Surface Elevation Measured at GPA-26 (River Mile +0.8, Front River)
3-4	Water Surface Elevation Measured At GPA-03 (River Mile +5.5, South Channel)
3-5	Water Surface Elevation Measured At GPA-02 (River Mile +4.5, Front River)
3-6	Water Surface Elevation Measured At GPA-25 (River Mile +5.5, Fields Cut)
3-7	Water Surface Elevation Measured At GPA-24 (River Mile +7.5, Elbe Island Cut)
3-8.....	Water Surface Elevation Measured At GPA-23 (River Mile +8.8, Wilmington River)
3-9.....	Water Surface Elevation Measured At GPA-04 (River Mile +10.4, Front River)
3-10.....	Water Surface Elevation Measured At GPA-21 (River Mile +13.9, Front River)
3-11	Water Surface Elevation Measured At GPA-05 (River Mile +14.5, Back River)
3-12.....	Water Surface Elevation Measured At GPA-06 (River Mile +16.6, Front River)
3-13.....	Water Surface Elevation Measured At GPA-22 (River Mile +18.7, Front River)
3-14.....	Water Surface Elevation Measured At GPA-08 (River Mile +20.5, Front River)
3-15.....	Water Surface Elevation Measured At GPA-09 (River Mile +21.5, Front River)
3-16.....	Water Surface Elevation Measured At GPA-11R (River Mile +23.4, Front River)
3-17.....	Water Surface Elevation Measured At GPA-14 (River Mile +27.7, Front River)
3-18.....	Water Surface Elevation Measured At GPA-18 (River Mile +28.9, Abercorn Creek)
3-19.....	Water Surface Elevation Measured At GPA-19 (River Mile +30.5, Abercorn Creek)

3-20	Water Surface Elevation Measured At GPA-20 (River Mile +31.2, Abercorn Creek)
3-21	Water Surface Elevation Measured At GPA-16 (River Mile +30.2, Savannah River)
3-22	Water Surface Elevation Measured At GPA-17 (River Mile 43.0, Savannah River)
3-23a	Current Magnitude near Surface, Mid-Depth, and Near Bottom at GPA-04 (River Mile +10.4, Front River)
3-23b	Primary Axis Velocities Near Surface, Mid-Depth, and Near Bottom at GPA-04 (River Mile +10.4, Front River)
3-24a	Current Magnitude near Surface, Mid-Depth, and Near Bottom at GPA-06 (River Mile +16.6, Front River)
3-24b	Primary Axis Velocities Near Surface, Mid-Depth, and Near Bottom at GPA-06 (River Mile +16.6, Front River)
3-25	Current Magnitude near Surface, Mid-Depth, and Near Bottom at GPA-14 (River Mile +27.7, Front River)
3-26	Current Magnitude near Surface, Mid-Depth, and Near Bottom at GPA-18 (River Mile +28.9, Abercorn Creek)
3-27	Current Magnitude near Surface, Mid-Depth, and Near Bottom at GPA-19 (River Mile +30.5, Abercorn Creek)
3-28	Current Magnitude near Surface, Mid-Depth, and Near Bottom at GPA-20 (River Mile +31.2, Abercorn Creek)
3-29	Current Magnitude near Surface, Mid-Depth, and Near Bottom at GPA-16 (River Mile +30.2, Savannah River)
3-30	Current Magnitude near Surface, Mid-Depth, and Near Bottom at GPA-17 (River Mile +43.0, Savannah River)
4-1a	Location of ADCP Transects (downstream of I-95 Bridge)
4-1b	Location of ADCP Transects (upstream of I-95 Bridge)
4-2	Photos of ADCP Data Collection
4-3	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect EIE (September 24, 1999)
4-4	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect EIW (September 24, 1999)
4-5	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect WR (September 24, 1999)
4-6	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect SCU (September 24, 1999)
4-7	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FJ (August 21, 1999)
4-8	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FJ (September 26, 1999)
4-9	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FJ (October 7, 1999)
4-10	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect BR (August 21, 1999)
4-11	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect BR (September 26, 1999)
4-12	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect BR (October 7, 1999)
4-13	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FR3 (August 21, 1999)
4-14	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FR3 (September 26, 1999)
4-15	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FR3 (October 7, 1999)
4-16	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood

	Velocity Profiles at Transect FW6 (October 18, 1999)
4-17	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW6 (October 26, 1999)
4-18	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW5 (October 18, 1999)
4-19	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW5 (October 26, 1999)
4-20	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW4 (October 18, 1999)
4-21	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW4 (October 26, 1999)
4-22	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FR2 (August 22, 1999)
4-23	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FR2 (September 25, 1999)
4-24	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FR2 (October 8, 1999)
4-25	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect MR2 (August 22, 1999)
4-26	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect MR2 (September 25, 1999)
4-27	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect MR2 (October 8, 1999)
4-28	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect LBR2 (August 22, 1999)
4-29	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect LBR2 (September 25, 1999)
4-30	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect LBR2 (October 8, 1999)
4-31	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW3 (October 19, 1999)
4-32	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW3 (October 25, 1999)
4-33	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW2 (October 19, 1999)
4-34	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW2 (October 25, 1999)
4-35	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW2U (October 19, 1999)
4-36	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW2U (October 25, 1999)
4-37	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW1 (October 19, 1999)
4-38	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FW1 (October 25, 1999)
4-39	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect LBR1 (September 29, 1999)

4-40	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect LBR1 (October 6, 1999)
4-41	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect MR1 (September 29, 1999)
4-42	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect MR1 (October 6, 1999)
4-43	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect UC (September 29, 1999)
4-44	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect UC (October 6 24, 1999)
4-45	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect MC (September 29, 1999)
4-46	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect MC (October 6, 1999)
4-47	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FR1 (September 29, 1999)
4-48	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect FR1 (October 6, 1999)
4-49	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect KC (September 29, 1999)
4-50	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect KC (October 6 1999)
4-51	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect I-95 (September 29, 1999)
4-52	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect I-95 (October 6, 1999)
4-53	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect GPA-14 (October 4, 1999)
4-54	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect GPA-18 (October 4, 1999)
4-55	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect GPA-19 (October 4, 1999)
4-56	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect GPA-20 (October 4, 1999)
4-57	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect GPA-16 (October 4, 1999)
4-58	Measured Flow over the Tidal Cycle, Maximum Ebb and Flood Velocity Profiles at Transect GPA-17 (October 4, 1999)
5-1a	Location of Continuous Water Quality Instruments (downstream of I-95 Bridge)
5-1b	Location of Continuous Water Quality Instruments (downstream of I-95 Bridge)
5-2	Photos of Continuous Water Quality Data Collection
5-3	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-26, Bottom Measurement (RM +0.8)
5-4	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-26, Surface Measurement (RM +0.8)
5-5	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-03, Bottom Measurement (RM +5.5)
5-6	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-02, Bottom Measurement (RM +4.5)

5-7	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-02, Surface Measurement (RM +4.5)
5-8	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-25, Mid-Depth Measurement (RM +5.5)
5-9	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-24, Mid-Depth Measurement (RM +7.5)
5-10	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-23, Mid-Depth Measurement (RM +8.8)
5-11	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-04, Bottom Measurement (RM +10.4)
5-12	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-04, Surface Measurement (RM +10.4)
5-13	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-21, Bottom Measurement (RM +13.9)
5-14	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-21, Surface Measurement (RM +13.9)
5-15	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-05, Bottom Measurement (RM +14.5)
5-16	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-06, Bottom Measurement (RM +16.6)
5-17	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-06, Surface Measurement (RM +16.6)
5-18	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-22, Bottom Measurement (RM +18.7)
5-19	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-22, Surface Measurement (RM +18.7)
5-20	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-07, Surface Measurement (RM +18.9)
5-21	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-08, Bottom Measurement (RM +20.5)
5-22	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-08, Surface Measurement (RM +20.5)
5-23	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-09, Bottom Measurement (RM +21.5)
5-24	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-09, Surface Measurement (RM +21.5)
5-25	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-10, Surface Measurement (RM +21.8)
5-26	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-15, Surface Measurement (RM +20.9)
5-27	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-11R, Bottom Measurement (RM +23.4)
5-28	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-12R, Surface Measurement (RM +23.7)
5-29	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-14, Bottom Measurement (RM +27.7)
5-30	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-16, Mid-Depth Measurement (RM +30.2)
5-31	Measured Temperature, Salinity, and Dissolved Oxygen at GPA-17, Mid-Depth Measurement (RM +43.0)
6-1a	Location of Meteorological Stations (downstream of I-95 Bridge)
6-1b	Location of Meteorological Stations (upstream of I-95 Bridge)
6-2	Location of Clio Gauging Station (RM +61.0)
6-3	Photos of Meteorological Data Collection
6-4	Measured Flow at Savannah River near Clio, Georgia USGS Station 02198500 for Year 1999 and Summer Deployment

	Period
6-5	Air Temperature, Wind Speed, and Wind Direction At GPA-26 (RM +0.8)
6-6	Rainfall, Barometric Pressure, Solar Radiation, and Relative Humidity GPA-26 (RM +0.8)
6-7	Air Temperature, Wind Speed, and Wind Direction At GPA-21 (RM +13.9)
6-8	Rainfall, Barometric Pressure, Solar Radiation, and Relative Humidity at GPA-21 (RM +13.9)
6-9	Air Temperature, Wind Speed, and Wind Direction At GPA-17 (RM +43.0)
6-10	Rainfall, Barometric Pressure, Solar Radiation, and Relative Humidity at GPA-17 (RM +43.0)
7-1	Location of Chloride and Bromide Instruments
7-2	Photos of Chloride/Bromide Data Collection
7-3	Chloride, Specific Conductance, and Water Surface Elevation At GPA-09 (Bottom)
7-4	Chloride, Specific Conductance, and Water Surface Elevation At GPA-11R (Bottom)
7-5	Chloride, Specific Conductance, and Water Surface Elevation At GPA-14 (Bottom)
7-6	Chloride, Specific Conductance, and Water Surface Elevation At GPA-18 (Bottom)
7-7	Chloride, Specific Conductance, and Water Surface Elevation At GPA-19 (Bottom)
7-8	Chloride, Specific Conductance, and Water Surface Elevation At GPA-20 (Bottom)
7-9	Chloride, Specific Conductance, and Water Surface Elevation At GPA-16 (Mid-Depth)
7-10	Chloride, Specific Conductance, and Water Surface Elevation At GPA-17 (Mid-Depth)
7-11	Chloride, Specific Conductance, and Water Surface Elevation At GPA-14 (Bottom)
7-12	Chloride, Specific Conductance, and Water Surface Elevation At GPA-18 (Bottom)
7-13	Chloride, Specific Conductance, and Water Surface Elevation At GPA-19 (Bottom)
8-1a	Location of Water Chemistry Sample Stations (downstream of I-95 Bridge)
8-1b	Location of Water Chemistry Sample Stations (downstream of I-95 Bridge)
8-2	Photos of Water Chemistry Sample Collection
8-3	Scatter Plot and Probability Distribution Plot of BOD5 Data (Weeks 1 to 7)
8-4	Scatter Plot and Probability Distribution Plot of CBOD Data (Weeks 1 to 7)
8-5	Scatter Plot and Probability Distribution Plot of Ammonia Data (Weeks 1 to 7)

8-6	Scatter Plot and Probability Distribution Plot of Nitrate-Nitrite Data (Weeks 1 to 7)
8-7	Scatter Plot and Probability Distribution Plot of TKN Data (Weeks 1 to 7)
8-8	Scatter Plot and Probability Distribution Plot of Total Phosphorus Data (Weeks 1 to 7)
8-9	Scatter Plot and Probability Distribution Plot of Orthophosphate Data (Weeks 1 to 7)
9-1	Location of EPD Longitudinal Profile Stations
9-2	Longitudinal Profile of Salinity and Dissolved Oxygen on September 13, 1999 at Cross-Sectional Points A and B
9-3	Longitudinal Profile of Salinity and Dissolved Oxygen on September 13, 1999 at Cross-Sectional Points C and D
9-4	Longitudinal Profile of Salinity on September 20, 1999 at High- and Low-Slack Tides
9-5	Longitudinal Profile of Dissolved Oxygen on September 20, 1999 At High- and Low-Slack Tides
9-6	Longitudinal Profile of Salinity on September 27, 1999 at High- and Low-Slack Tides
9-7	Longitudinal Profile of Dissolved Oxygen on September 27, 1999 At High- and Low-Slack Tides
9-8	Longitudinal Contours of Dissolved Oxygen on September 13, 1999
9-9	Longitudinal Contours of Salinity on September 13, 1999
9-10	Longitudinal Contours of Dissolved Oxygen at High Slack Tide on September 20, 1999
9-11	Longitudinal Contours of Salinity at High Slack Tide on September 20, 1999
9-12	Longitudinal Contours of Dissolved Oxygen at Low Slack Tide on September 20, 1999
9-13	Longitudinal Contours of Salinity at Low Slack Tide on September 20, 1999
9-14	Longitudinal Contours of Dissolved Oxygen at Low- and High-Slack Tides on September 27, 1999
9-15	Longitudinal Contours of Salinity at High Slack Tide on September 27, 1999
9-16	Longitudinal Contours of Salinity at Low Slack Tide on September 27, 1999
9-17	Location of 24-Hour Dynamic Sampling Stations
9-18	Diurnal Variations in BOD5, TKN, Nitrate-Nitrite, Ammonia, Total-P, and Ortho-P at Station 24HR-01 (Bottom & Surface)
9-19	Diurnal Variations in Dissolved Oxygen and Salinity at Station 24HR-01 (Bottom & Surface)
9-20	Diurnal Variations in BOD5, TKN, Nitrate-Nitrite, Ammonia, Total-P, and Ortho-P at Station 24HR-02 (Bottom & Surface)
9-21	Diurnal Variations in Dissolved Oxygen and Salinity at Station 24HR-02 (Bottom & Surface)
9-22	Diurnal Variations in BOD5, TKN, Nitrate-Nitrite, Ammonia, Total-P, and Ortho-P at Station 24HR-03 (Mid-Depth)
9-23	Diurnal Variations in Dissolved Oxygen and Salinity at Station 24HR-03 (Mid-Depth)
9-24	Diurnal Variations in BOD5, TKN, Nitrate-Nitrite, Ammonia, Total-P, and Ortho-P at Station 24HR-04 (Mid-Depth)
9-25	Diurnal Variations in Dissolved Oxygen and Salinity at Station 24HR-04 (Mid-Depth)
9-26	Locations of Marsh Exchange Transects

9-27	Nutrient Data Measured at Marsh Transect 1 on September 9, 1999
9-28	Salinity and Dissolved Oxygen Measured at Marsh Transect 1 on September 9, 1999
9-29	Nutrient Data Measured at Marsh Transect 2 on September 21, 1999
9-30	Salinity and Dissolved Oxygen Measured at Marsh Transect 2 on September 21, 1999
9-31	Nutrient Data Measured at Marsh Transect 3 on September 9, 1999
9-32	Salinity and Dissolved Oxygen Measured at Marsh Transect 3 on September 9, 1999
9-33	Nutrient Data Measured at Marsh Transect 4 on September 21, 1999
9-34	Salinity and Dissolved Oxygen Measured at Marsh Transect 4 on September 21, 1999
9-35	Nutrient Data Measured at Marsh Transect 5 on September 9, 1999
9-36	Salinity and Dissolved Oxygen Measured at Marsh Transect 5 on September 9, 1999
9-37	Longitudinal Profiles of Chlorophyll-a Concentrations within, at and below the Photic Zone on September 22-23, 1999
10-1	Long-term Biochemical Oxygen Demand Composite Samples
10-2	LTBOD Test Results: BOD and NBOD at LTBOD-01 for Weeks 2, 4, and 6
10-3	LTBOD Test Results: BOD and NBOD at LTBOD-02 for Weeks 2, 4, and 6
10-4	LTBOD Test Results: BOD and NBOD at LTBOD-03 for Weeks 2, 4, and 6
10-5	LTBOD Test Results: BOD and NBOD at LTBOD-04 for Weeks 2, 4, and 6
10-6	LTBOD Test Results: BOD and NBOD at LTBOD-05 for Weeks 2, 4, and 6
10-7	LTBOD Test Results: BOD and NBOD at LTBOD-06 for Weeks 2, 4, and 6
10-8	LTBOD Test Results: BOD and NBOD at CLYO for Weeks 2, 4, and 6
10-9	LTBOD Test Results: Comparison of BOD Data from LTBOD Stations for Week 2 (August 11, 1999)
10-10	LTBOD Test Results: Comparison of BOD Data from LTBOD Stations for Week 4 (August 25, 1999)
10-11	LTBOD Test Results: Comparison of BOD Data from LTBOD Stations for Week 6 (September 8, 1999)
10-12	LTBOD Test Results: Marsh Exchange Transect T1 (September 22, 1999)
10-13	LTBOD Test Results: Marsh Exchange Transect T2 (September 22, 1999)
10-14	LTBOD Test Results: Marsh Exchange Transect T3 (September 22, 1999)
10-15	LTBOD Test Results: Marsh Exchange Transect T4 (September 22, 1999)
10-16	LTBOD Test Results: Marsh Exchange Transect T5 (September 22, 1999)
11-1a	Locations of USGS Continuous Monitoring Stations

11-1b	Locations of USGS Continuous Monitoring Stations
11-2	USGS Water Surface Elevation at 02198980 – Fort Pulaski (River Mile +0.8)
11-3.....	USGS Water Surface Elevation at 02198977 – Broad Street (River Mile +14.6)
11-4	USGS Water Surface Elevation at 02198920 – Port Wentworth (River Mile +21.5)
11-5	USGS Water Surface Elevation at 02198979 – Limehouse (River Mile +24.2)
11-6	USGS Water Surface Elevation at 02198840 – I-95 Bridge (River Mile +27.7)
11-7	USGS Water Surface Elevation at 02198760 – Hardeeville (River Mile +39.0)
11-8.....	GPA26B (RM 0.8) and USGS – Fort Pulaski (RM 0.8) Water Surface Elevation
11-9.....	GPA02B (RM 4.5) and USGS – Fort Pulaski (RM 0.8) Water Surface Elevation
11-10	GPA03B (RM 5.5) and USGS – Fort Pulaski (RM 0.8) Water Surface Elevation
11-11	GPA25M (RM 5.5) and USGS – Fort Pulaski (RM 0.8) Water Surface Elevation
11-12	GPA24M (RM 7.5) and USGS – Fort Pulaski (RM 0.8) Water Surface Elevation
11-13	GPA23M (RM 8.8) and USGS – Fort Pulaski (RM 0.8) Water Surface Elevation
11-14	GPA04B (RM 10.4) and USGS – Broad Street (RM 14.4) Water Surface Elevation
11-15	GPA21B (RM 13.9) and USGS – Broad Street (RM 14.4) Water Surface Elevation
11-16	GPA05B (RM 14.5) and USGS – Broad Street (RM 14.4) Water Surface Elevation
11-17	GPA06B (RM 16.6) and USGS – Broad Street (RM 14.4) Water Surface Elevation
11-18	GPA22B (RM 18.7) and USGS – Broad Street (RM 14.4) Water Surface Elevation
11-19	GPA08B (RM 20.5) and USGS – Broad Street (RM 14.4) Water Surface Elevation
11-20	GPA09B (RM 21.5) and USGS – Port Wentworth (Holihan Bridge) (RM 21.5) Water Surface Elevation
11-21	GPA11RB (RM 23.4) and USGS – Port Wentworth (Holihan Bridge) (RM 21.5) Water Surface Elevation
11-22	GPA14B (RM 27.7) and USGS – I-95 Bridge (RM 27.7) Water Surface Elevation
11-23	GPA18B (RM 28.9) and USGS – I-95 Bridge (RM 27.7) Water Surface Elevation
11-24	GPA19B (RM 30.5) and USGS – I-95 Bridge (RM 27.7) Water Surface Elevation
11-25	GPA20B (RM 31.2) and USGS – I-95 Bridge (RM 27.7) Water Surface Elevation
11-26	GPA16M (RM 30.2) and USGS – I-95 Bridge (RM 27.7) Water Surface Elevation
11-27	GPA14B (RM 43) and USGS – Hardeeville (RM 39) Water Surface Elevation
11-28	USGS Salinity at 02198920- Port Wentworth (River Mile (RM 21.5)
11-29	USGS Salinity at 021989791 – US Fish and Wildlife Dock (River Mile +22.1)

- 11-30..... USGS Salinity at 02198979 – Limehouse
(River Mile +24.2)
- 11-31..... USGS Salinity at 02198840 – I-95 Bridge
(River Mile +27.7)

ACKNOWLEDGEMENTS

The 1999 data collection effort described herein is a product of collaboration with numerous agencies and professionals. The GPA contracted with ATM and the Savannah District, USACE to design and implement this data collection program as part of the Savannah Harbor Expansion Project. A subcommittee of the Stakeholder Evaluation Group (SEG), called the Modeling Technical Review Group (MTRG), provided technical review and input for the design and implementation of the data collection program. The MTRG is comprised of leading modeling experts and technical representatives from the following groups:

- United States Environmental Protection Agency (USEPA), Region IV
- Georgia Environmental Protection Division (GAEPD)
- South Carolina Department of Health and Environmental Control (SCDHEC)
- United States Army Corps of Engineers (USACE), Savannah District Office
- USACE, Waterways Experiment Station (WES)
- United States Geological Survey (USGS)
- South Carolina Department of Natural Resources (SCDNR)
- Georgia Cooperative Unit
- Harbor Committee
- City of Savannah
- United States Fish and Wildlife Service (USFW), Savannah Coastal Refuge
- Skidaway Institute of Oceanography (SKIO)
- Coastal Environmental Organization (CEO)

Other groups that contributed to the accomplishment of this data collection effort, that are not listed above, are the following:

- Georgia Ports Authority (GPA)
- Lares Undersea Contracting, Inc.
- USACE Savannah Depot Facility
- United States Coast Guard (USCG)
- Savannah Bar Pilot Station
- Georgia and South Carolina Department of Transportation
- C.C. Lynch and Associates, Inc.
- Coastal Leasing
- Burns Environmental Services
- University of Florida Coastal and Oceanographic Laboratory

- Savannah Laboratories
- Analytical Environmental Services
- Columbia Analytical Services
- USFWS, Savannah National Wildlife Refuge